

NOTES

1. DO NOT SCALE FROM DRAWING.
2. ALL TIMBER SHALL BE IN ACCORDANCE WITH CLAUSES 306 & 311 OF THE MCHW AND BS EN 351-1:1996.
3. ALL METAL PARTS SHALL BE IN ACCORDANCE WITH THE APPROPRIATE CLAUSES IN THE MCHW 300 SERIES AND BS 5709:2006.
4. HANDRAILS ARE TO BE KEE KLAMP SIZE 8 OR EQUIVALENT.
5. ENDS OF BRIDGES TO BE 0 TO 75 MM ABOVE GROUND LEVEL. FOR SLOPING SITES HEIGHTS ABOVE GROUND LEVEL TO BE AGREED BY THE OVERSEEING ORGANISATION.
6. END POSTS OF HANDRAILS TO BE DRIVEN INTO BANKS.
7. IF BRIDGE IS 3 METRES OR LESS, THEN NO INTERMEDIATE UPRIGHT ON HAND-RAIL(S).
8. IF BRIDGE IS BETWEEN 3 METRES AND 4 METRES THEN ONE INTERMEDIATE UPRIGHT HANDRAIL-POST, TO BE CENTRED.
9. IF BRIDGE IS 4 METRES OR OVER THEN INTERMEDIATE UPRIGHT HANDRAIL-POSTS ARE TO BE SPACED EVENLY BETWEEN 2 AND 3 METRES APART.
10. ALL HAND-RAILS ARE TO HAVE AN INTERMEDIATE RAIL AT 1100MM HIGH FOR FOOTPATHS AND THE TOP-RAIL AT 1400MM HIGH FOR BRIDLEWAYS.
11. HAND-RAILS ARE TO BE PROVIDED ON BOTH SIDES.

Rev.	Date	Description of revision	Drawn	Checked	Review'd	Approv'd

DRAWING STATUS

APPROVED

Essex Highways

Essex Highways, Seax House, Victoria Road South,
Chelmsford, CM1 1QH.
Tel: 0345 6037631
© Essex County Council

SCHEME TITLE

STANDARD DETAILS

DRAWING TITLE

STANDARD PEDESTRIAN BRIDGE - DECKED TYPE 3

DESIGNED	DRAWN	CHECKED	REVIEWED	APPROVED
EH	IS	EH/ECC	EH	ECC
DATE	DATE	DATE	DATE	DATE
AUG 18	AUG 18	FEB 19	FEB 19	FEB 19

DRAWING UNITS U.N.O.
DIMENSIONS IN MILLIMETRES
LEVELS IN METRES

SCALE AT A3 (420x297mm)
N.T.S

DRAWING No.
ECC-SD-2600-003

REV.
-

Essex County Council